



**EQUIPMENT ANCHORAGE
& SEISMIC ENGINEERING**

5877 Pine Ave, Ste. 210
Chino Hills, CA. 91709
Phn: (909) 606-7622

The Department of Health Care Access and Information

PREAPPROVAL OF MANUFACTURER'S CERTIFICATION

OPM-0757

THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE

MANUFACTURER: **DOOR SYSTEMS INC**
EQUIPMENT NAME: **DSI-FW-W119 ELEVATOR SMOKE AND FIRE CURTAIN**

Sheet: 1 of 9

Date: 4/30/25

GENERAL NOTES

1. THIS HCAI PREAPPROVAL OF MANUFACTURER'S CERTIFICATION (OPM) IS BASED ON THE 2022 CBC. THE DEMANDS (DESIGN FORCES) FOR USE WITH THIS OPM SHALL BE BASED ON THE 2022 CBC
2. THIS DOCUMENT MAY ONLY BE USED WITH THE EXPRESS WRITTEN CONSENT OF THE MANUFACTURER LISTED ABOVE FOR THE SPECIFIC PROJECT SITE AND INSTALLATION LOCATION. THIS DOCUMENT IS INVALID WITHOUT SUCH CONSENT.
3. THIS PREAPPROVAL CONFORMS TO THE 2022 CALIFORNIA BUILDING CODE WHERE S_{ds} IS NOT GREATER THAN 1.60, 2.00.
4. FORCES PER ASCE 7-16 SECTION 13.3.1, EQUATIONS 13.3-1, 13.3-2 & 13.3-3,
WHERE $S_{ds} = 1.60$ $a_p = 1.0$, $I_p = 1.5$, $R_p = 1.5$, $z/h \leq 1$ CONCRETE WALL. SEE FOLLOWING SHEETS FOR Ω_0 .
WHERE $S_{ds} = 2.00$ $a_p = 1.0$, $I_p = 1.5$, $R_p = 1.5$, $z/h \leq 1$ CONCRETE WALL. SEE FOLLOWING SHEETS FOR Ω_0 .
5. THIS PREAPPROVAL COVERS ONLY THE SUPPORTS AND ATTACHMENTS OF THE EQUIPMENT TO THE STRUCTURE.
6. ALL DESIGN FORCES SHOWN ON THE DRAWINGS ARE FACTORED LOADS THAT SHALL BE USED FOR STRENGTH DESIGN.
7. SHEET METAL SCREWS SHALL BE TEKS SCREWS BY ITW BULDEX (ICC ESR-1976).
8. CONCRETE WALL DETAIL VALID FOR DEMANDS SHOWN AT ANY ELEVATION. (i.e. $z/h \leq 1$)
9. REFER TO ESR-4761 FOR DSI 600 SYSTEM'S FIRE AND SMOKE PROTECTION APPROVAL.
10. **RESPONSIBILITIES OF THE STRUCTURAL ENGINEER OF RECORD OF THE BUILDING**
 - A. PROVIDE SUPPORTING STRUCTURE TO SUPPORT WEIGHTS AND FORCES SHOWN IN ADDITION TO ALL OTHER LOADS.
 - B. VERIFY THAT THE INSTALLATION IS IN CONFORMANCE WITH THE 2022 CBC AND WITH THE DETAILS, MATERIAL AND GAGE OF THE UNIT WHERE ATTACHMENTS ARE MADE AGREE WITH THE INFORMATION SHOWN ON THE PREAPPROVAL DOCUMENTS.
 - C. VERIFY THAT PROJECT SPECIFIC VALUES OF S_{ds} & z/h RESULT IN SEISMIC FORCES (E_h , E_v) THAT DO NOT EXCEED THE VALUES ON THE DETAILS.
 - D. VERIFY THAT THE CONCRETE WALL TO WHICH THE EQUIPMENT IS ANCHORED MEETS THE REQUIREMENTS OF THE APPLICABLE ICC ESR AND THIS OPM.
 - E. VERIFY THAT THE ANCHORS ARE AN ADEQUATE DISTANCE FROM ANY CONCRETE WALL EDGES OR OPENINGS (SEE TYPICAL DETAIL ON SHEET 2).
 - F. VERIFY THAT ALL NEW OR EXISTING ANCHORS ARE AN ADEQUATE DISTANCE FROM THE UNIT ATTACHMENTS AND CHECK FOR INTERACTION WHERE OTHER ANCHORS ARE WITHIN 18" OR $6h_{ef}$ FROM THIS UNIT'S ANCHORS.
 - G. DESIGN BACKING BARS, STUDS, ETC. WHICH THE UNITS ARE ATTACHED TO AS NOTED ON THE DRAWINGS.



HCAI APPROVAL PENDING

DOOR SYSTEMS INC

DSI-FW-W119 ELEVATOR SMOKE AND FIRE CURTAIN

DES. **J. ROBERSON**

JOB NO. **11-2503**

DATE **4/30/25**

SHEET

2

OF **9** SHEETS

11. EXPANSION ANCHORS:

- A. ATTACHMENT IS TO BE MADE WITH THE ANCHORS LISTED BELOW AND INSTALLED AS DESCRIBED IN THE CORRESPONDING ICC REPORT.

Anchor Diameter	Concrete Type	Min. f'c (psi)	Anchor Type	ICC Report No.	Min. Embed.	Min. Spacing	Min. + Edge Dist.	Min. Conc. Thickness	Torque Test	Direct Tension
3/8"	Normal Weight	3000	Hilti Kwik Bolt TZ2 (CARBON STEEL)	ESR-4266	2"	6"	14"	4"	30 FT-LB	1982 lb

- B. THIS PREAPPROVAL ALLOWS FOR UP TO A MAXIMUM OF 2 ADJACENT CONCRETE SLAB EDGES, 8" AWAY MINIMUM (i.e. - CORNER). SEE ADJACENT DETAIL FOR ADDITIONAL MINIMUM ALLOWABLE CONCRETE EDGE DISTANCES.

+ FOOTNOTE: MINIMUM ALLOWABLE EDGE DISTANCE OF 2.5" AT GUIDE RAILS ONLY


- C. TESTING AND SPECIAL INSPECTION OF EXPANSION ANCHORS SHALL BE PERFORMED BY AN APPROVED INDEPENDENT AGENCY EMPLOYED BY THE FACILITY OWNER PER CBC 1704A & 1910A.5 AND CAC 7-149. ALL REPORTS SHALL BE SENT TO THE INSPECTOR OF RECORD, OWNER AND THE ARCHITECT OR ENGINEER IN RESPONSIBLE CHARGE.

- (i) AFTER AT LEAST 24 HOURS HAVE ELAPSED SINCE INSTALLATION, DIRECT PULL TENSION TEST AT LEAST 50% OF THE ANCHORS.

- (ii) ACCEPTANCE CRITERIA:

- DIRECT TENSION TEST: THE ANCHOR SHOULD HAVE NO OBSERVABLE MOVEMENT AT THE TEST LOAD. A PRACTICAL WAY TO DETERMINE OBSERVABLE MOVEMENT IS THAT THE WASHER BECOMES LOOSE.
- TORQUE TEST: THE APPLICABLE TORQUE MUST BE ACHIEVED WITHIN THE FOLLOWING LIMITS: WEDGE TYPE : 1/2 TURN OF THE NUT

- (iii) IF ANY ANCHOR FAILS, TEST ALL ANCHORS.



TYPICAL CONCRETE EDGE DETAIL



HCAI APPROVAL PENDING

DOOR SYSTEMS INC

DSI-FW-W119 ELEVATOR SMOKE AND FIRE CURTAIN

DES. J. ROBERSON

JOB NO. 11-2503

DATE 4/30/25

SHEET


3

OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED

HEADBOX
(18 GA, A653,
Fy=30 KSI MIN)
(BY MFR)



USE #14 TEK SCREWS AT 16" O.C. MAX
W 3/16" x 1/4" FENDER WASHERS
(TOP, MIDDLE & BOTTOM, 18)
TO STEEL STUD WALL
OR
USE 3/8" HILTI KB-TZ2 (CS)
EXPANSION ANCHORS
(MIN. EMBED. (he) = 2") @ 36" O.C.
W 1/2" x 1/4" FENDER WASHERS
(TOP, MIDDLE & BOTTOM)
TO CONCRETE WALL
(BY STRUCTURAL ENGINEER OF RECORD)

STRUCTURAL ENGINEER OF RECORD
SHALL DESIGN THE BACKING
PLATE (16 GA., 50 KSI MIN.)
AND THE WALL STRUCTURE

SEE SHEET 7 OF 7

"A"

"A"

#10 TEK SCREWS

SIDE GUIDE
(11 GA, A653, Fy=30 KSI MIN)
(BY MFR) (2 TOTAL)

NOTES:

- FORCES ARE DETERMINED PER 2022 CALIFORNIA BUILDING CODE AND ASCE 7-16. STRENGTH DESIGN IS USED. (EXAMPLE: $a_p = 1.0$, $I_p = 1.5$, $R_p = 1.5$, $z/h \leq 1$)

Sds	1.60	2.00
HORIZONTAL FORCE (E_h)	1.92 W_p	2.40 W_p
HORIZONTAL FORCE (E_{mh})	3.84 W_p	4.80 W_p
VERTICAL FORCE (E_v)	0.32 W_p	0.40 W_p

- THIS CALCULATION ENCOMPASSES WEIGHTS AND C.G. POSITIONS NOT EXCEEDING VALUES SHOWN.
- THIS CALCULATION WAS PREPARED WITHOUT KNOWLEDGE OF ANY SITE CONDITION. COMPATIBILITY FOR USE WITH A SITE SHALL BE EVALUATED BY THE STRUCTURAL ENGINEER OF RECORD OF THE INSTALLATION (SEOR). USE REQUIRES APPROVAL BY THE SEOR.
- STRUCTURAL ENGINEER OF RECORD FOR THE INSTALLATION SHALL VERIFY ALL CONDITIONS, EVALUATE INTERACTION WITH ADJACENT EQUIPMENT AND ANCHORS, AND PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEETS 1 AND 2



HCAI APPROVAL PENDING

DOOR SYSTEMS INC

DSI-FW-W119 ELEVATOR SMOKE
AND FIRE CURTAIN

DES. J. ROBERSON

JOB NO. 11-2503

DATE 4/30/25

SHEET


4

OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

 $S_{DS} \leq 1.60$

WALL MOUNTED



HCAI APPROVAL PENDING

DOOR SYSTEMS INC

**DSI-FW-W119 ELEVATOR SMOKE
AND FIRE CURTAIN**

DES. **J. ROBERSON**

JOB NO. **11-2503**

DATE **4/30/25**

SHEET


5

OF **9** SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

$S_{DS} \leq 2.00$

WALL MOUNTED



Jonathan Roberson

REGISTERED PROFESSIONAL ENGINEER
JONATHAN ROBERSON
No. 4197
EXP. 6-30-2026
4/30/25
STRUCTURAL
STATE OF CALIFORNIA

HCAI APPROVAL PENDING

DOOR SYSTEMS INC

DSI-FW-W119 ELEVATOR SMOKE AND FIRE CURTAIN

DES. J. ROBERSON

JOB NO. 11-2503

DATE 4/30/25


SHEET

6

OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED



ELEVATION (MULTIPLE CURTAINS)

NOTES:

- FORCES ARE DETERMINED PER 2022 CALIFORNIA BUILDING CODE AND ASCE 7-16. STRENGTH DESIGN IS USED. (EXAMPLE: $a_p = 1.0$, $l_p = 15$, $R_p = 15$, $z/h \leq 1$)

S_{ds}	1.60	2.00
HORIZONTAL FORCE (E_h)	1.92 W_p	2.40 W_p
HORIZONTAL FORCE (E_{mh})	3.84 W_p	4.80 W_p
VERTICAL FORCE (E_v)	0.32 W_p	0.40 W_p

- THIS CALCULATION ENCOMPASSES WEIGHTS AND C.G. POSITIONS NOT EXCEEDING VALUES SHOWN.
- THIS CALCULATION WAS PREPARED WITHOUT KNOWLEDGE OF ANY SITE CONDITION. COMPATIBILITY FOR USE WITH A SITE SHALL BE EVALUATED BY THE STRUCTURAL ENGINEER OF RECORD OF THE INSTALLATION (SEOR). USE REQUIRES APPROVAL BY THE SEOR.
- STRUCTURAL ENGINEER OF RECORD FOR THE INSTALLATION SHALL VERIFY ALL CONDITIONS, EVALUATE INTERACTION WITH ADJACENT EQUIPMENT AND ANCHORS, AND PROVIDE SUPPORT STRUCTURE DESIGNED TO SUPPORT WEIGHTS AND FORCES SHOWN IN COMBINATION WITH ALL OTHER LOADS THAT MAY BE PRESENT.
- SEE GENERAL NOTES: SHEETS 1 AND 2



HCAI APPROVAL PENDING

DOOR SYSTEMS INC

DSI-FW-W119 ELEVATOR SMOKE
AND FIRE CURTAIN

DES. J. ROBERSON

JOB NO. 11-2503

DATE 4/30/25

SHEET



7

OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

 $Sds \leq 1.60$

WALL MOUNTED



HCAI APPROVAL PENDING

DOOR SYSTEMS INC

DSI-FW-W119 ELEVATOR SMOKE
AND FIRE CURTAIN

DES. J. ROBERSON

JOB NO. 11-2503

DATE 4/30/25

SHEET


8

OF 9 SHEETS

SEISMIC SUPPORTS & ATTACHMENTS

 $S_Ds \leq 2.00$

WALL MOUNTED



HCAI APPROVAL PENDING

DOOR SYSTEMS INC

DSI-FW-W119 ELEVATOR SMOKE AND FIRE CURTAIN

DES. J. ROBERSON

JOB NO. 11-2503

DATE 4/30/25

SHEET

9

OF 9 SHEETS


SEISMIC SUPPORTS & ATTACHMENTS

WALL MOUNTED

STRUCTURAL ENGINEER OF RECORD
SHALL DESIGN THE BACKING
PLATE (16 GA., 50 KSI MIN.)
AND THE WALL STRUCTURE


USE #14 TEK SCREWS
W/ STANDARD WASHERS
TO STEEL STUD WALL
(BY STRUCTURAL ENGINEER OF RECORD)

5/8" THK
WALL BOARD
(2 LAYER MAX)



SECTION AT STEEL STUD WALL

USE 3/8"Φ HILTI KB-TZ2 (CS)
EXPANSION ANCHORS
(MIN. EMBED. (h_{ef}) = 2")
W/ STANDARD WASHERS
TO CONCRETE WALL
(BY STRUCTURAL ENGINEER
OF RECORD)



SECTION AT CONCRETE WALL
SECTION A-A



HCAI APPROVAL PENDING